

# Development of high current highly charged laser ion source

FY23, FY24, FY25(NCE)


Maashiro Okamura (BNL), Guy Garty (Columbia University)

November 17, 2025

## Project goals

- Develop Laser ion source (LIS) and Radio Frequency Quadrupole (RFQ).
- Very high current and highly charged state ion beam will be delivered.
- Use Direct Plasma Injection Scheme which was invented by the PI.
- Target species are from light to medium mass ions.

## laser ion source (LIS)




Plasma Formation

Plasma Expansion

- High density plasma created from a solid.
- Fast switching target materials.
- Low temperature after adiabatic expansion.
- Uniform density of beams.

## Direct Plasma Injection Scheme (DPIS)



- Dense expanding plasma from solid targets.
- Retaining high brightness, heavy ions can be delivered to RFQ.
- Since ions in plasma state, space charge effect can be neglected.
- No focusing lenses.
- No high voltage cage, no isolating transformer.

Performance of DPIS was verified by some limited species.  
We explore possibility to accelerate heavy ions with DPIS.  
This work will give a benchmark for future accelerator project.

## Project Status (control milestones)

### FY2023-Q1

- 1 Subcontract with Columbia University  
Dec. 31, 2022 **Dec. 22**
- 2 Open call for a postdoc position  
Dec. 31, 2022 **Oct. 4 Madhawa joined Sep. 1 2023**

### FY2023-Q2

- 1 The first beam through the RFQ  
Feb. 28, 2023 **Feb. 10 (<sup>11</sup>B<sup>5</sup>)**

### FY2023-Q3

- 1 The second species acceleration  
Jun. 30, 2023 **Jun. 30 (<sup>12</sup>C<sup>6</sup>)**
- 2 Design of new laser irradiation box  
Jun. 30, 2023 **May 20**

### FY2023-Q4

- 1 Design of RFQ electrodes  
Sep. 30, 2023 **Sep. 30**
- 3 Presentation at international conference  
Sep. 30, 2023 **Sep. 30, 5 presentations at ICIS2023**

### FY2024-Q1

- 1 Procurement of new electrodes type 1  
Dec. 31, 2023 **Mar. 2024 Procurement placed**
- 2 The third species acceleration  
Dec. 31, 2023 **Sep. 20 (<sup>26</sup>Mg<sup>10</sup>)**

### FY2024-Q2

- 1 Installation of type 1 electrodes  
Mar. 30, 2024 **Nov. 10**
- 2 The forth species acceleration  
Mar. 30, 2024 **Mar. 25 10 (<sup>27</sup>Al<sup>11</sup>)**

### FY2024-Q3

- 1 Procurement of new electrodes type 2  
Jun. 30, 2024 **Nov. 21**

### FY2024-Q4

- 1 Installation of electrodes type 2  
Aug. 30, 2024 **TBD**
- 2 The fifth species acceleration  
Sep. 30, 2024 **Oct. 3 (<sup>28</sup>Si<sup>12</sup>)**

### FY2025-Q2

- 1 Procurement of type 2  
Mar. 30, 2025 **Feb. 28 Procurement placed**
- 2 Design of type 2 electrodes  
Jan. 31, 2025 **Dec. 31, 2024**

### FY2025-Q3

- 1 Paper submission  
Apr. 30, 2025 **submitted**
- 2 Design of chamber  
May. 31, 2025 **Jan. 15**
- 3 Fifth species acceleration  
May. 15, 2025 **TBD**



### FY2025-Q4

- 1 International conference report  
Aug. 31, 2025 **HIAT25 invited talk**
- 2 Fabrication of target station  
Aug. 31, 2025 **Being fabricated**
- 3 Installation of target station  
Sep. 15, 2025 **TBD**
- 4 Installation of type 2 electrodes  
Sep. 15, 2025 **TBD**
- 5 First species acceleration  
Sep. 30, 2025 **TBD**


Summary of expenditures by fiscal year (FY):

	FY23 (\$K)	FY24 (\$K)	FY25 (\$K)	Total (\$K)
a) Funds allocated	400	400	N/A	800
b) Actual costs to date	256	269	73	598


# Laser Ion Source and RFQ



Dipole magnet



RFQ accelerator



Plasma Chamber

# FY25, Accelerated Species

Original and Type I RFQ



$\text{Al}^{11+}$  58 mA

Type-1 electrodes


$\text{C}^{6+}$  97 mA

Al



# Beam Extraction Region



# Detailed aluminum beam acceleration




58 mA of  $\text{Al}^{11+}$  beam was achieved after optimization



# Original RFQ design



Parameter	Value
Structure	4 Rod
Frequency	100 MHz
Input energy	22 keV/n
Output energy	204 keV/n
Input beam current	50 mA
Number of cells	138
Input emittance (norm., 100%)	1 pi mm mrad
Transmission	80 % (40 mA)
RFQ length	1977 mm
V (for ${}^7\text{Li}^{3+}$ )	59 kV
R0	4.5 mm
Transverse vane-tip curvature	0.75 R0
Kilpatrick factor	1.5



RFQ linac was designed with parmtaq (constant voltage and  $R_0$ ) for 40 mA output

Accelerated beam current was limited by the RFQ design

So, New RFQ was developed for higher beam current


# Type-1 RFQ design

## Design criteria

- Max  $m/q = 7/3$  (assuming  ${}^7\text{Li}^{3+}$ )
- Target output peak current  $> 100$  emA
- Extraction voltage  $\sim 50$  kV
- 100 MHz
- Transmission  $\sim 75\%$  inter-vane voltage of 105 kV
- Kilpatrick factor less than 2
- 2 m long
- Output energy above 300 keV/n


## Variable focusing force strategy

Resonant frequency	100 MHz
Accelerated particle	${}^7\text{Li}^{3+}$
Peak beam current	$\geq 100$ emA
Input energy	21.8 keV/u
Output energy	320 keV/u
Input normalized rms emittance	0.33 mmmrad
Number of cells	138
Rod length	1997.5 mm
V	105 kV
$r_0$ (without RMS)	6.2-7.8 mm
Transverse vane-tip curvature	Variable ( $\leq 1.0r_0$ )
$E_{\text{max}}$ (Kilpatrick factor)	$\leq 22.3$ MV/m (1.96)





Vane voltage is always constant, but the beam aperture varies from place to place.

## 2D simulation along beam axis for 3D simulation





Simulate to have a same capacitance in every cross-section.



The cross-sectional shape of Vane varies with location.

## Full 3D simulation





Full 3D calculation vs. forced constant voltage

Resonant frequency	94.86 MHz (94.99 MHz)
Unloaded Q value	3324.3
$E_{max}$ (Kilpatrick factor)	$\leq 24.8$ MV/m (2.18 kilp)


## Type-1 electrodes installation




## Type-1 electrodes Low power RF tuning



## Perturbation Positions




## Completion of Type-1 electrodes Low power RF tuning




Desired voltage distribution was achieved with desired resonant frequency

## Type-1 RFQ electrodes ready for high power test




With high power test, 300 kW was achieved.

## Record-breaking 97 mA Carbon 6+ beam with Type-1 electrodes




96 mA Carbon 6+ beam was achieved after optimization  
 $4 \times 10^{10}$  particles

## Extraction Voltage and Bias Voltage Optimization



## Solenoid B-field Optimization



## Conclusion (Major deliverables up to now)

1. Aluminum(  $\text{Al}^{11+}$ ) peak current exceeds 55 mA
2. Type-1 RFQ electrodes were delivered
3. Low power and high power test were completed
4. Type-1 RFQ electrodes were commissioned with C beam
5. Record-breaking 96 mA of  $\text{C}^{6+}$  beam was achieved
7. Continuing beam acceleration with Type-1 RFQ electrodes
8. New target station is being fabricated

**Thank you for your  
attention**

